BILLS OF QUANTITIES

IKEJA CORPORATE OFFICE

PREPARED BY	Demo Partners QS
MEASURED FROM	Ikeja_Office.ifc
METHOD	BESMM4R; Nigerian elements
CURRENCY	Nigerian Naira
DATE	03 November 2026

General Summary

Ref	Description	Amount (₦)
A	Preliminaries (5% of measured work)	44,697,976.24
B	Main Building	889,361,197.79
C	M&E Services	4,598,327.00
D	External Works	0.00
	Sub-total	938,657,501.03
	Contingency 5%	46,932,875.05
	VAT 7.5%	73,919,278.21
	TOTAL CARRIED TO FORM OF TENDER	1,059,509,654.29

Notes

Quantities are measured from the building models (IFC) by code, to BESMM4R, and grouped into the items below.
Every item traces to the model elements it was measured from.
Rates are from the firm's rate library; an item without a rate is left blank for pricing and adds nothing.
Preliminaries, contingency and VAT are percentages on the summary, never inside the rates.
17 items have no rate yet.

BILL B: MAIN BUILDING

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
B1	**SUBSTRUCTURE**				
A	Reinforced in-situ concrete (1:2:4 - 19mm aggregate) in ground floor slab	743.51	m³	142,471.00	105,928,755.68
B	Timber-finished ground-bearing floor construction (specification to be confirmed)	239.40	m²		
C	Excavation for ground slabs and footings, not exceeding 1.50m deep	1,055.96	m³	4,725.00	4,989,392.10
D	300mm thick compacted laterite hardcore filling	527.98	m³		
E	12mm diameter high yield bars to ground slabs and edge thickening	59.48	t	1,303,234.00	77,517,661.55
F	Formwork to edges of ground floor slab	117.90	m²	5,071.00	597,881.04
G	1000 gauge polythene damp-proof membrane under ground floor slab	1,759.93	m²	525.00	923,961.67
H	Anti-termite treatment to soil under foundations and ground floor slab	1,759.93	m²	1,426.00	2,509,655.90
B2	**FRAME**				
A	Precast reinforced concrete beams 300 x 600mm (concrete mix to be confirmed)	52.81	m³	317,670.00	16,776,788.04
B	Reinforced in-situ concrete (1:2:4 - 19mm aggregate) in 300mm diameter circular columns	43.35	m³	151,415.00	6,564,294.50
C	Reinforced in-situ concrete (1:2:4 - 19mm aggregate) in 450mm diameter circular columns	1.75	m³	151,415.00	264,219.17
D	Structural steel open-web bar joists 8K1: supply, fabricate, prime, hoist and erect	1.21	t	3,190,550.00	3,873,327.70
E	Structural steel curved beam: supply, fabricate, prime, hoist and erect	0.80	t	3,437,875.00	2,760,613.62
F	Structural steel wide-flange beams (UB sections) W310 x 28.3kg/m: supply, fabricate, prime, hoist and erect	0.47	t	3,011,188.00	1,409,235.98
G	Structural steel wide-flange columns (UC sections) W250X49.1: supply, fabricate, prime, hoist and erect	0.96	t	3,029,825.00	2,914,691.65
H	High yield reinforcement to columns and beams	11.75	t	1,303,234.00	15,311,696.27
J	Formwork to sides of columns	592.96	m²	9,189.00	5,448,672.68
B3	**UPPER FLOORS**				
A	Hollow-core plank floor with concrete topping and carpet finish to upper floors (plank thickness, topping thickness/mix and carpet specification to be confirmed)	3,247.53	m²		
B4	**STAIRS**				
A	Reinforced in-situ concrete (1:2:4 - 19mm aggregate) in staircases and stair landings	32.89	m³	154,770.00	5,090,230.53
B	900mm high metal pipe guard rail to stairs, mild steel tube, painted	126.32	m	42,456.00	5,363,126.83
C	Metal handrail 900mm high to stairs, mild steel tube on wall brackets, painted	28.03	m	18,773.00	526,244.74
D	Metal pipe guard rail to floors and stair landings, mild steel tube, painted (height to be confirmed)	123.91	m	42,456.00	5,260,680.50
E	Steel stair stringer, 50mm wide, primed and fixed	104.61	m		
F	12mm diameter high yield bars to stair flights and landings	2.63	t	1,303,234.00	3,428,808.65
G	Formwork to soffits and sides of staircases	247.96	m²	13,293.00	3,296,158.87
B5	**WALLS**				

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
A	138mm thick metal stud partition with plasterboard lining; 1-hour fire rating	2,887.67	m²	57,093.00	164,865,743.31
B	Reinforced in-situ concrete (1:2:4 - 19mm aggregate) in 225mm thick walls	14.36	m³	151,415.00	2,174,925.06
C	Concrete block parapet wall with external thermal insulation; block thickness and mortar to be confirmed	168.82	m²	30,746.00	5,190,662.70
D	External concrete block wall with thermal insulation and internal plasterboard lining; block thickness and mortar to be confirmed	783.64	m²	40,661.00	31,863,708.02
E	Formwork to faces of walls	148.20	m²	10,317.00	1,528,979.40
B6	**ROOF**				
A	Concrete deck roof with tapered insulation and EPDM waterproofing membrane; thicknesses to be confirmed	1,592.59	m²		
B7	**WINDOWS**				
A	30mm square aluminium curtain wall mullion, supply and install	193.00	m		
B	50 x 150mm aluminium curtain wall mullion, supply and install	4,344.75	m	31,436.00	136,581,592.44
C	Black-anodized aluminium L-corner mullion to curtain wall, supply and install	85.16	m		
D	Fixed glazed window 915mm wide x 1220mm high, framing to be confirmed, supply and install	24.00	nr		
E	Glazed panel to curtain walling/sloped glazing, supply and install	2,206.98	m²	53,731.00	118,583,081.19
F	Solid granite-faced panel to curtain walling, supply and install	349.22	m²	81,371.00	28,416,380.62
B8	**DOORS**				
A	Powder-coated aluminium glazed doors/screens, supply and install (specialist); double-leaf aluminium-framed glazed curtain wall door, 1830 x 2136mm	6.00	nr	732,250.00	4,393,500.00
B	Double-leaf flush door set, 1730 x 2134mm; frame, ironmongery, material and finish to be confirmed	1.00	nr		
C	Double-leaf flush door set including frame and ironmongery, 1730 x 2134mm, 20 minute fire rated; material and finish to be confirmed	4.00	nr	691,688.00	2,766,752.00
D	Double-leaf flush door set including frame and ironmongery, 1830 x 2134mm; material and finish to be confirmed	2.00	nr	452,350.00	904,700.00
E	Double-leaf glazed door set including frame and ironmongery, 1830 x 2134mm; frame material, glazing type and finish to be confirmed	1.00	nr	570,688.00	570,688.00
F	Powder-coated aluminium glazed doors/screens, supply and install (specialist); single-leaf aluminium-framed glazed curtain wall door, 915 x 2134mm	11.00	nr	366,125.00	4,027,375.00
G	Single-leaf double-acting flush door set including frame and ironmongery, 915 x 2134mm; material and finish to be confirmed	1.00	nr	346,650.00	346,650.00
H	Single-leaf flush door set with vision light including frame and ironmongery, 915 x 2134mm; material and finish to be confirmed	4.00	nr	285,260.00	1,141,040.00
J	Single-leaf flush door set including frame and ironmongery, 915 x 2134mm; material and finish to be confirmed	63.00	nr	253,500.00	15,970,500.00
K	Single-leaf flush door set including frame and ironmongery, 915 x 2134mm, 20 minute fire rated; material and finish to be confirmed	6.00	nr	374,500.00	2,247,000.00
L	Single-leaf glazed door set including frame and ironmongery, 915 x 2134mm; frame material, glazing type and finish to be confirmed	1.00	nr	318,260.00	318,260.00
B9	**FLOOR FINISHES**				
A	40mm thick cement and sand (1:4) screed to floors	3,247.53	m²		

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
B10	**WALL FINISHES**				
A	12mm thick cement and sand (1:6) plaster to block walls	2,184.61	m²		
B11	**CEILING FINISHES**				
A	600 x 600mm suspended acoustic ceiling tiles on aluminium grid	2,732.64	m²	17,436.00	47,646,380.78
B	Plasterboard lining to furred ceiling on metal furring	921.99	m²	9,697.00	8,940,507.94
C	Plasterboard lining to plain ceiling	30.64	m²	9,697.00	297,145.17
B12	**PAINTING AND DECORATION**				
A	Emulsion painting to partitions and ceilings	13,084.60	m²	3,044.00	39,829,528.49
B13	**FITTINGS AND FURNISHINGS**				
A	Window shade blind including fixings, supply and fix (size to be confirmed)	6.00	nr		
	TOTAL OF BILL B CARRIED TO SUMMARY				889,361,197.79

BILL C: M&E SERVICES

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
C1	**ELECTRICAL INSTALLATIONS**				
A	Lighting point: conduit, 1.5 mm² wiring (12 m run), switch share, 2440mm long linear pendant fitting with 1 lamp	30.00	nr	126,347.00	3,790,410.00
B	Lighting point: conduit, 1.5 mm² wiring (12 m run), switch share, table lamp with 60W incandescent lamp	4.00	nr	71,347.00	285,388.00
C	Lighting point: conduit, 1.5 mm² wiring (12 m run), switch share, wall sconce fitting with 40W halogen lamp	7.00	nr	74,647.00	522,529.00
	TOTAL OF BILL C CARRIED TO SUMMARY				4,598,327.00

BILL D: EXTERNAL WORKS

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
D1	**EXTERNAL WORKS**				
A	Perimeter sandcrete block fence wall and metal gates	1.00	item		
B	External surface drainage and manholes	1.00	item		
C	Septic tank and soakaway	1.00	item		
D	Borehole with pumps and overhead water tank	1.00	item		
E	Standby generator, generator house and external lighting	1.00	item		
	TOTAL OF BILL D CARRIED TO SUMMARY				0.00