BILLS OF QUANTITIES

IKOYI DUPLEX

PREPARED BY	Demo Partners QS
MEASURED FROM	Ifc2x3_Duplex_Architecture.ifc
METHOD	BESMM4R; Nigerian elements
CURRENCY	Nigerian Naira
DATE	03 November 2026

General Summary

Ref	Description	Amount (₦)
A	Preliminaries (5% of measured work)	4,673,555.72
B	Main Building	91,447,758.94
C	External Works	2,023,355.45
	Sub-total	98,144,670.11
	Contingency 5%	4,907,233.51
	VAT 7.5%	7,728,892.77
	TOTAL CARRIED TO FORM OF TENDER	110,780,796.39

Notes

Quantities are measured from the building models (IFC) by code, to BESMM4R, and grouped into the items below. Every item traces to the model elements it was measured from.
Rates are from the firm's rate library; an item without a rate is left blank for pricing and adds nothing.
Preliminaries, contingency and VAT are percentages on the summary, never inside the rates.

BILL B: MAIN BUILDING

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
B1	**SUBSTRUCTURE**				
A	1000 gauge damp-proof membrane laid to floor	124.55	m²	525.00	65,386.65
B	Reinforced in-situ concrete (mix to be confirmed) in ground floor slab; 127mm thick	16.47	m³	142,471.00	2,346,497.37
C	Reinforced in-situ concrete (mix to be confirmed) in foundation walls; 417mm thick	26.86	m³	149,181.00	4,007,150.84
D	Reinforced in-situ concrete (mix to be confirmed) in foundation walls; 435mm thick	5.43	m³	149,181.00	810,052.83
E	Anti-termite soil treatment to bottoms of excavation and under slabs	179.64	m²	1,426.00	256,166.64
F	Well-sawn plank formwork to slab edges, kerbs and concrete upstands	2.02	m²	5,071.00	10,258.63
G	Traditional well-sawn plank formwork to below-ground concrete in foundation walls	144.48	m²	4,400.00	635,707.60
H	Traditional well-sawn plank formwork to below-ground concrete in foundations	36.19	m²	4,400.00	159,231.60
J	Plain in-situ concrete (1:3:6) blinding 50mm thick under foundations	55.09	m²	5,499.00	302,956.41
K	Reinforced in-situ concrete (mix to be confirmed) in pad and strip foundations; 900 x 300mm strip footings	16.53	m³	146,383.00	2,419,418.22
B2	**UPPER FLOORS**				
A	19mm plywood subfloor sheathing to upper floors	118.56	m²	17,180.00	2,036,912.34
B	286mm deep timber floor joists at centres to be confirmed to upper floors	118.56	m²	23,180.00	2,748,290.34
B3	**STAIRS**				
A	1100mm high metal guard railing to staircase	16.67	m	52,982.00	883,156.96
B	900mm high metal handrail to staircase	9.49	m	18,773.00	178,137.00
C	Stair flight with 200mm maximum riser and 250mm tread; material to be confirmed	2.00	nr	825,288.00	1,650,576.00
D	Stair stringers; material and section size to be confirmed	15.00	m	85,616.00	1,284,240.00
B4	**WALLS**				
A	136mm deep metal stud framing to walls at centres (stud spacing to be confirmed)	58.56	m²	9,202.00	538,841.51
B	152mm deep metal stud framing to walls at centres (stud spacing to be confirmed)	9.39	m²	11,979.00	112,482.81
C	16mm plasterboard lining to walls, screwed, joints taped and filled	695.77	m²	11,872.00	8,260,228.93
D	193mm thick concrete block inner leaf in mortar (mortar mix to be confirmed)	272.00	m²	21,013.00	5,715,514.99
E	193mm thick concrete blockwork in mortar (mortar mix to be confirmed)	131.09	m²	21,013.00	2,754,615.18
F	38mm deep metal stud framing to walls at centres (stud spacing to be confirmed)	2.56	m²	4,121.00	10,529.16
G	41mm deep metal stud framing to walls at centres (stud spacing to be confirmed)	403.09	m²	4,363.00	1,758,686.03
H	50mm thick rigid thermal insulation to walls (method of fixing to be confirmed)	272.00	m²	12,218.00	3,323,283.78
J	92mm deep metal stud framing to walls at centres (stud spacing to be confirmed)	106.40	m²	7,269.00	773,392.52

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
K	92mm thick brick outer leaf in mortar (mortar mix and brick type to be confirmed)	272.00	m²	57,896.00	15,747,654.10
B5	**ROOF**				
A	Flat timber joist roof deck forming part of green roof (joist sizes to be confirmed)	132.93	m²	48,798.00	6,486,522.95
B6	**WINDOWS**				
A	Fixed glazed window 2800 x 2410mm high, framing to be confirmed, supply and install	4.00	nr	978,717.00	3,914,868.00
B	Fixed glazed window 4835 x 2420mm high, framing to be confirmed, supply and install	2.00	nr	1,698,012.00	3,396,024.00
C	Fixed glazed window 750 x 2200mm high, framing to be confirmed, supply and install	4.00	nr	244,853.00	979,412.00
D	Fixed glazed window 819 x 759mm high, framing to be confirmed, supply and install	12.00	nr	99,073.00	1,188,876.00
E	Glazed roof skylight window 1173 x 635mm high, framing to be confirmed, supply and install	2.00	nr	144,167.00	288,334.00
B7	**DOORS**				
A	Timber flush door set: 1250 x 2010mm single leaf, hardwood frame/lining, architraves, ironmongery, lacquer finish	2.00	nr	292,000.00	584,000.00
B	Timber flush door set: 762 x 2032mm single leaf, hardwood frame/lining, architraves, ironmongery, lacquer finish	4.00	nr	253,500.00	1,014,000.00
C	Timber flush door set: 864 x 2032mm single leaf, hardwood frame/lining, architraves, ironmongery, lacquer finish	6.00	nr	253,500.00	1,521,000.00
D	Single-leaf glazed door set 813 x 2420mm, supply and install including frame/lining, architraves and ironmongery; frame material, glazing and finish to be confirmed	2.00	nr	380,100.00	760,200.00
B8	**FLOOR FINISHES**				
A	10mm thick ceramic tile floor finish (tile size to be confirmed)	44.91	m²	11,280.00	506,584.80
B	16mm thick timber strip flooring (species and fixing to be confirmed)	196.92	m²	27,020.00	5,320,805.42
C	3mm thick semi-rigid insulation underlay to timber flooring	196.92	m²	1,826.00	359,577.75
B9	**CEILING FINISHES**				
A	12mm thick flat gypsum-board suspended ceiling	243.46	m²	18,562.00	4,519,067.40
B	45mm deep metal stud framing to ceiling; centres to be confirmed	243.46	m²	7,472.00	1,819,118.18
	TOTAL OF BILL B CARRIED TO SUMMARY				91,447,758.94

BILL C: EXTERNAL WORKS

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
C1	**EXTERNAL WORKS**				
A	150mm thick reinforced in-situ concrete (mix to be confirmed) in exterior ground slab	7.63	m³	142,471.00	1,086,483.85
B	Formwork to edges of suspended slabs (type to be confirmed)	4.52	m²	5,071.00	22,920.92
C	Formwork to soffits of suspended slabs (type to be confirmed)	50.84	m²	17,977.00	913,950.68
	TOTAL OF BILL C CARRIED TO SUMMARY				2,023,355.45