BILLS OF QUANTITIES

LEKKI OFFICE BLOCK

PREPARED BY	Demo Partners QS
MEASURED FROM	Office_ARC.ifc, Office_STR.ifc, Office_ELE.ifc
METHOD	BESMM4R; Nigerian elements
CURRENCY	Nigerian Naira
DATE	03 November 2026

General Summary

Ref	Description	Amount (₦)
A	Preliminaries (5% of measured work)	64,189,521.43
B	Main Building	835,814,997.65
C	M&E Services	447,975,431.00
	Sub-total	1,347,979,950.08
	Contingency 5%	67,398,997.50
	VAT 7.5%	106,153,421.07
	TOTAL CARRIED TO FORM OF TENDER	1,521,532,368.66

Notes

Quantities are measured from the building models (IFC) by code, to BESMM4R, and grouped into the items below. Every item traces to the model elements it was measured from.
Rates are from the firm's rate library; an item without a rate is left blank for pricing and adds nothing.
Preliminaries, contingency and VAT are percentages on the summary, never inside the rates.

BILL B: MAIN BUILDING

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
B1	**SUBSTRUCTURE**				
A	Reinforced in-situ concrete (1:2:4 - 19mm aggregate) in pad and strip foundations	85.92	m³	146,383.00	12,577,666.51
B	Reinforced in-situ concrete (1:2:4 - 19mm aggregate) in foundation walls	55.49	m³	149,181.00	8,278,053.69
C	Reinforced in-situ concrete (1:2:4 - 19mm aggregate) in ground floor slab	228.99	m³	142,471.00	32,624,861.70
D	Formwork to sides of foundations	183.83	m²	4,400.00	808,838.80
E	Plain in-situ concrete (1:3:6) blinding 50mm thick under foundations	172.34	m²	5,499.00	947,708.66
F	Anti-termite treatment to soil under foundations and ground floor slab	1,972.29	m²	1,426.00	2,812,482.69
G	Formwork to edges of ground floor slab	1.18	m²	5,071.00	5,988.85
H	1000 gauge polythene damp-proof membrane under ground floor slab	1,799.95	m²	525.00	944,971.65
J	Formwork to faces of foundation walls	348.05	m²	4,400.00	1,531,415.60
B2	**FRAME**				
A	Structural steel open-web bar joists, 12K3 section	2.46	t	3,190,550.00	7,861,515.20
B	Structural steel open-web bar joists, 14K1 section	18.23	t	3,190,550.00	58,157,345.40
C	Structural steel wide-flange beams, W360X44 section	1.88	t	3,011,188.00	5,651,999.88
D	Structural steel wide-flange beams, W460X60 section	54.95	t	3,011,188.00	165,476,825.35
E	Structural steel wide-flange columns, W250X67 section	22.75	t	3,029,825.00	68,919,429.28
B3	**UPPER FLOORS**				
A	Profiled metal decking to upper floor slab, 38mm deep	1,782.06	m²	17,945.00	31,978,976.98
B	Reinforced lightweight in-situ concrete on metal decking, 64mm thick	114.05	m³	143,585.00	16,376,156.42
C	Formwork to edges of suspended slabs	21.25	m²	5,071.00	107,753.68
B4	**STAIRS**				
A	Metal guard railing 1100mm high to stairs	12.31	m	52,982.00	652,473.33
B	Metal handrail 900mm high to stairs	34.78	m	18,773.00	652,962.49
C	900mm high metal pipe guard rail to stairs	9.37	m	42,456.00	397,600.44
D	Concrete-pan stair flight; 180mm maximum riser 280mm tread	4.00	nr	3,722,386.00	14,889,544.00
E	Reinforced in-situ concrete (1:2:4 - 19mm aggregate) in stair landings	0.24	m³	154,770.00	37,454.34
F	Steel stair stringer	21.75	m	85,616.00	1,861,976.77
G	Formwork to soffits and sides of staircases	5.52	m²	13,293.00	73,430.53
B5	**WALLS**				
A	152mm metal stud framing to external walls	1,683.50	m²	11,979.00	20,166,646.50
B	16mm Type-X fire-rated plasterboard lining	662.04	m²	15,262.00	10,104,100.27
C	16mm plasterboard lining	9,061.21	m²	11,872.00	107,574,661.38
D	19mm plywood sheathing to external walls	1,643.12	m²	16,795.00	27,596,200.40
E	38mm metal furring to walls	100.46	m²	3,382.00	339,765.87
F	38mm metal stud framing to walls	882.91	m²	4,121.00	3,638,467.99
G	42mm insulated wall panels	100.46	m²	36,138.00	3,630,531.89
H	90mm facing brickwork in cement and sand (1:4) mortar	1,542.66	m²	57,896.00	89,313,727.57

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
J	92mm metal stud framing to internal partitions	3,558.23	m²	7,269.00	25,864,781.14
B6	**ROOF**				
A	EPDM roofing membrane on rigid thermal insulation (thickness to be confirmed) on profiled metal roof decking (thickness to be confirmed) to roof slab	199.73	m²	49,345.00	9,855,824.88
B	Standing seam metal roof covering (thickness to be confirmed) on profiled metal roof decking (thickness to be confirmed) on steel bar joists to roof slab	94.07	m²	38,785.00	3,648,349.81
B7	**WINDOWS**				
A	Fixed glazed window, 1000 x 1000mm, glazed (frame material to be confirmed)	2.00	nr	153,774.00	307,548.00
B	Fixed glazed window, 1000 x 2000mm, glazed (frame material to be confirmed)	1.00	nr	294,682.00	294,682.00
C	Fixed glazed window, 1200 x 1500mm, glazed (frame material to be confirmed)	65.00	nr	266,500.00	17,322,500.00
D	Fixed glazed window, 3500 x 1000mm, glazed (frame material to be confirmed)	1.00	nr	506,044.00	506,044.00
B8	**DOORS**				
A	Double-leaf flush door set, 1830 x 2083mm, complete with ironmongery (material to be confirmed)	4.00	nr	452,350.00	1,809,400.00
B	Double-leaf flush door set, 1830 x 2134mm, complete with ironmongery (material to be confirmed)	2.00	nr	452,350.00	904,700.00
C	Single-leaf flush door set, 915 x 2134mm, complete with ironmongery (material to be confirmed)	87.00	nr	253,500.00	22,054,500.00
D	Toilet cubicle door set, 813 x 1525mm, complete with ironmongery (material to be confirmed)	5.00	nr	117,812.00	589,060.00
E	Toilet cubicle door set, 915 x 1525mm, complete with ironmongery (material to be confirmed)	4.00	nr	117,812.00	471,248.00
B9	**CEILING FINISHES**				
A	45mm deep metal stud framing to suspended ceiling; centres to be confirmed	38.10	m²	7,472.00	284,720.56
B	600 x 600mm acoustic ceiling tiles, 16mm thick to suspended ceilings	3,078.16	m²	17,436.00	53,670,797.76
C	12mm thick plasterboard lining to suspended ceilings	38.10	m²	9,697.00	369,504.18
B10	**FITTINGS AND FURNISHINGS**				
A	25mm thick laminate toilet cubicle partition panels	20.59	m²	90,798.00	1,869,803.21
	TOTAL OF BILL B CARRIED TO SUMMARY				835,814,997.65

BILL C: M&E SERVICES

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
C1	**SANITARY INSTALLATIONS**				
A	Semi-recessed paper towel dispenser with receptacle, supply and fix	5.00	nr	212,179.00	1,060,895.00
B	Supply (PC sum) and fix stainless steel grab rail	8.00	nr	43,664.00	349,312.00
C	Supply (PC sum) and fix toilet paper holder	10.00	nr	16,022.00	160,220.00
C2	**PLUMBING AND DRAINAGE**				
A	380 litre water heater supplied and installed	1.00	nr	2,729,235.00	2,729,235.00
C3	**MECHANICAL INSTALLATIONS**				
A	Air-cooled screw chiller, 633-703kW capacity, supplied and installed	1.00	nr	209,820,500.00	209,820,500.00
B	Horizontal split system air handling unit, 63300000J capacity, supplied and installed	2.00	nr	15,329,400.00	30,658,800.00
C	Inline circulator pump, 3.9 litres/second 0.8m head, supplied and installed	1.00	nr	3,945,850.00	3,945,850.00
D	Roof-mounted upblast centrifugal fan, 991-1905 litres/second, supplied and installed	1.00	nr	5,423,850.00	5,423,850.00
C4	**ELECTRICAL INSTALLATIONS**				
A	225A lighting and appliance distribution board	9.00	nr	493,880.00	4,444,920.00
B	Lighting point: PVC conduit, wiring, switch and back box, with pendant linear 2-lamp light fitting, 1200mm long	2.00	nr	85,922.00	171,844.00
C	Lighting point: PVC conduit, wiring, switch and back box, with pendant linear 2-lamp light fitting, 2400mm long	12.00	nr	158,676.00	1,904,112.00
D	Lighting point: PVC conduit, wiring, switch and back box, with plain recessed light fitting, 600 x 1200mm	269.00	nr	120,847.00	32,507,843.00
E	Lighting point: PVC conduit, wiring, switch and back box, with plain recessed light fitting, 600 x 600mm	47.00	nr	82,347.00	3,870,309.00
F	Single pole lighting switch supplied and fixed	94.00	nr	8,376.00	787,344.00
G	Three way lighting switch supplied and fixed	5.00	nr	8,926.00	44,630.00
H	Transformer switchboard, 914 x 673mm	2.00	nr	5,382,240.00	10,764,480.00
J	Twin socket outlet point: PVC conduit and wiring	441.00	nr	77,507.00	34,180,587.00
C5	**LIFT INSTALLATIONS**				
A	Centre-opening lift entrance door, 48 x 84 inch, supplied and installed	2.00	nr	4,329,100.00	8,658,200.00
B	Hydraulic passenger lift, 3500 lbs capacity, supplied and installed	1.00	nr	96,492,500.00	96,492,500.00
	TOTAL OF BILL C CARRIED TO SUMMARY				447,975,431.00