BILLS OF QUANTITIES

IKEJA CORPORATE OFFICE

PREPARED BY	Demo Partners QS
CLIENT	Ikeja Holdings Ltd
LOCATION	Ikeja, Lagos
MEASURED FROM	Ikeja_Office.ifc
METHOD	BESMM4R; Nigerian elements
CURRENCY	Nigerian Naira
DATE	04 November 2026

General Summary

Ref	Description	Amount (₦)
A	Preliminaries (5% of measured work)	59,966,523.32
B	Main Building	1,193,915,311.39
C	M&E Services	5,415,155.00
	Sub-total	**1,259,296,989.71**
	Contingency 5%	**62,964,849.49**
	VAT 7.5%	**99,169,637.94**
	TOTAL CARRIED TO FORM OF TENDER	**1,421,431,477.13**

Notes

Quantities are measured from the building models (IFC) by code, to BESMM4R, and grouped into the items below. Every item traces to the model elements it was measured from.
Rates are from the firm's rate library; an item without a rate is left blank for pricing and adds nothing.
Preliminaries, contingency and VAT are percentages on the summary, never inside the rates.

BILL B: MAIN BUILDING

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
B1	**SUBSTRUCTURE**				
A	1000 gauge polythene damp-proof membrane under ground floor slab	1,999.33	m²	525.00	1,049,646.68
B	Anti-termite treatment to soil under foundations and ground floor slab	1,999.33	m²	1,430.00	2,859,037.61
C	Formwork to edges of ground floor slab, not exceeding 250mm high	30.26	m²	5,071.00	153,448.46
D	Reinforced in-situ concrete (mix to be confirmed) in ground floor slab	209.51	m³	142,782.00	29,914,114.04
B2	**FRAME**				
A	Formwork to sides of circular columns	580.87	m²	9,189.00	5,337,605.24
B	Precast concrete rectangular beam, 300 RB 600, 35 MPa concrete (mix, reinforcement and joint details to be confirmed)	52.81	m³	318,101.00	16,799,550.01
C	Reinforced in-situ concrete (mix to be confirmed) in circular columns	45.10	m³	151,732.00	6,842,809.74
D	Steel K-series bar joist, 8K1 (span, bearings, finish and connection details to be confirmed)	1.21	t	3,197,040.00	3,881,206.56
E	Structural steel curved beam (section and connection details to be confirmed)	0.80	t	3,444,919.00	2,766,269.96
F	Structural steel wide-flange beams, W310X28.3 section	0.47	t	3,017,241.00	1,412,068.79
G	Structural steel wide-flange columns, W250X49.1 section	0.96	t	3,035,891.00	2,920,527.14
B3	**UPPER FLOORS**				
A	Concrete topping to hollow-core floor (mix and thickness to be confirmed)	823.04	m³	143,896.00	118,431,588.26
B	Precast concrete hollow-core floor planks	3,105.80	m²	56,983.00	176,977,744.42
C	Reinforced in-situ concrete in slab edge (mix and reinforcement to be confirmed)	39.54	m³	143,896.00	5,689,647.84
B4	**STAIRS**				
A	900mm high pipe railing, metal-bronze (details to be confirmed)	126.32	m	45,294.00	5,721,628.67
B	900mm high wall-mounted pipe handrail, metal-bronze (details to be confirmed)	28.03	m	45,294.00	1,269,681.41
C	Formwork to soffits and sides of staircases	143.92	m²	13,293.00	1,913,168.44
D	Painted steel stair stringer, 50mm width (section and details to be confirmed)	104.61	m	85,802.00	8,975,918.82
E	Pipe guardrail, metal-bronze (height and details to be confirmed)	123.91	m	45,294.00	5,612,334.25
F	Reinforced in-situ concrete (mix to be confirmed) in stair flights (finish to be confirmed)	4.53	m³	155,089.00	701,932.81

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
G	Reinforced in-situ concrete (mix to be confirmed) in stair landings	0.71	m³	155,089.00	109,803.01
B5	**WALLS**				
A	138mm metal stud framing to internal partitions, 1-hour fire rating (stud size and details to be confirmed)	2,887.67	m²	57,216.00	165,220,926.72
B	Concrete block wall in cement and sand mortar (thickness and mix to be confirmed) in external and parapet walls	952.44	m²	21,053.00	20,051,803.53
C	External wall insulation (material and thickness to be confirmed) to external and parapet walls	952.44	m²	12,245.00	11,662,676.78
D	Formwork to faces of walls	147.33	m²	10,317.00	1,520,034.56
E	Reinforced in-situ concrete wall, 225mm thick (mix and reinforcement to be confirmed)	14.36	m³	151,732.00	2,179,478.45
B6	**ROOF**				
A	Concrete deck flat roof with tapered insulation and EPDM membrane (build-up, mix and thicknesses to be confirmed)	1,592.59	m²	39,279.00	62,555,146.22
B7	**WINDOWS**				
A	Aluminium L-corner curtain-wall mullion, black-anodized (section to be confirmed)	85.16	m	31,504.00	2,682,880.64
B	Aluminium curtain-wall mullion, 30mm square section, black-anodized	193.00	m	17,697.00	3,415,521.00
C	Aluminium curtain-wall mullion, 50 x 150mm section, black-anodized	4,344.75	m	31,504.00	136,877,035.50
D	Curtain-wall glazing, clear glass (thickness and type to be confirmed)	2,206.98	m²	53,842.00	118,828,055.63
E	Fixed glazed window, 915 x 1220mm, glazed (frame material to be confirmed)	24.00	nr	172,029.64	4,128,711.36
F	Solid granite-faced curtain-wall panel (thickness and backing to be confirmed)	349.22	m²	81,547.00	28,477,843.34
B8	**DOORS**				
A	Double-leaf flush door set, 1730 x 2134mm, complete with ironmongery (material to be confirmed)	1.00	nr	442,748.85	442,748.85
B	Double-leaf flush door set, 1830 x 2134mm, complete with ironmongery (material to be confirmed)	2.00	nr	453,311.00	906,622.00
C	Double-leaf flush fire door set, 1730 x 2134mm, 20 minute rated, complete with ironmongery (material to be confirmed)	4.00	nr	693,197.00	2,772,788.00
D	Double-leaf glazed aluminium curtain wall door set, 1830 x 2136mm, complete with ironmongery	6.00	nr	758,885.66	4,553,313.96
E	Double-leaf glazed door set, 1830 x 2134mm, complete with ironmongery (frame material to be confirmed)	1.00	nr	571,922.00	571,922.00
F	Single-leaf flush door set with vision panel, 915 x 2134mm, complete with ironmongery and glazing (material to be confirmed)	4.00	nr	285,860.00	1,143,440.00

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
G	Single-leaf flush door set, 915 x 2134mm, complete with ironmongery (material to be confirmed)	63.00	nr	254,034.00	16,004,142.00
H	Single-leaf flush double-acting door set, 915 x 2134mm, complete with ironmongery (material to be confirmed)	1.00	nr	347,379.00	347,379.00
J	Single-leaf flush fire door set, 915 x 2134mm, 20 minute rated, complete with ironmongery (material to be confirmed)	6.00	nr	375,309.00	2,251,854.00
K	Single-leaf glazed aluminium curtain-wall door set, 915 x 2134mm, complete with ironmongery	11.00	nr	379,075.38	4,169,829.18
L	Single-leaf glazed door set, 915 x 2134mm, complete with ironmongery (frame material to be confirmed)	1.00	nr	318,935.00	318,935.00
B9	**WALL FINISHES**				
A	Plasterboard lining to external walls (thickness to be confirmed)	783.62	m²	11,898.00	9,323,510.76
B	Plasterboard lining to internal partitions (thickness to be confirmed)	2,887.67	m²	11,898.00	34,357,497.66
B10	**FLOOR FINISHES**				
A	Carpet floor finish	3,105.80	m²	23,557.00	73,163,307.04
B	Timber / wood block floor finish (species and thickness to be confirmed)	239.40	m²	41,930.00	10,038,000.07
B11	**CEILING FINISHES**				
A	600 x 600mm acoustic ceiling tiles to suspended grid ceilings	2,732.64	m²	17,475.00	47,752,953.90
B	Plasterboard furred ceiling (thickness and framing to be confirmed)	921.99	m²	9,717.00	8,958,947.68
C	Plasterboard plain ceiling (thickness and framing to be confirmed)	30.64	m²	9,717.00	297,758.03
B12	**FITTINGS AND FURNISHINGS**				
A	Metal sunscreen / brise-soleil panels (details to be confirmed)	206.36	m²	93,610.00	19,317,172.38
B	Window blind (type and size to be confirmed), supplied and fixed	6.00	nr	47,224.00	283,344.00
	TOTAL OF BILL B CARRIED TO SUMMARY				**1,193,915,311.39**

BILL C: M&E; SERVICES

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
C1	**ELECTRICAL INSTALLATIONS**				
A	Pendant linear light fitting, 2440mm long (wiring and conduit to be confirmed)	30.00	nr	159,014.00	4,770,420.00
B	Wall-mounted sconce light fitting, 40 watt halogen (wiring and conduit to be confirmed)	7.00	nr	92,105.00	644,735.00
	TOTAL OF BILL C CARRIED TO SUMMARY				**5,415,155.00**