BILLS OF QUANTITIES

LEKKI OFFICE BLOCK

PREPARED BY	Demo Partners QS
CLIENT	Lekki Gardens Holdings
LOCATION	Lekki, Lagos
MEASURED FROM	Office_ARC.ifc, Office_ELE.ifc, Office_STR.ifc
METHOD	BESMM4R; Nigerian elements
CURRENCY	Nigerian Naira
DATE	04 November 2026

General Summary

Ref	Description	Amount (₦)
A	Preliminaries (5% of measured work)	65,662,953.09
B	Main Building	900,123,102.77
C	M&E Services	413,135,959.00
	Sub-total	**1,378,922,014.86**
	Contingency 5%	**68,946,100.74**
	VAT 7.5%	**108,590,108.67**
	TOTAL CARRIED TO FORM OF TENDER	**1,556,458,224.28**

Notes

Quantities are measured from the building models (IFC) by code, to BESMM4R, and grouped into the items below. Every item traces to the model elements it was measured from.
Rates are from the firm's rate library; an item without a rate is left blank for pricing and adds nothing.
Preliminaries, contingency and VAT are percentages on the summary, never inside the rates.

BILL B: MAIN BUILDING

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
B1	**SUBSTRUCTURE**				
A	1000 gauge polythene damp-proof membrane under ground floor slab	1,803.09	m²	525.00	946,624.35
B	Anti-termite treatment to soil under foundations and ground floor slab	1,975.44	m²	1,430.00	2,824,874.91
C	Formwork to edges of ground floor slab, not exceeding 250mm high	1.18	m²	5,071.00	5,988.85
D	Formwork to faces of foundation walls	348.03	m²	4,400.00	1,531,345.20
E	Formwork to sides of foundations, 250 - 500mm high	164.39	m²	4,400.00	723,302.80
F	In-situ concrete in ground floor slab on grade, 127mm thick (mix and reinforcement to be confirmed)	228.99	m³	142,782.00	32,696,078.53
G	Plain in-situ concrete (1:3:6) blinding 50mm thick under foundations	172.34	m²	5,499.00	947,708.66
H	Reinforced in-situ concrete (mix to be confirmed) in foundation walls, 300mm thick	55.49	m³	149,496.00	8,295,533.04
J	Reinforced in-situ concrete (mix to be confirmed) in pad and strip foundations	85.92	m³	146,696.00	12,604,560.41
B2	**FRAME**				
A	Steel bar joist, 12K3 section	2.46	t	3,197,040.00	7,877,506.56
B	Steel bar joist, 14K1 section	18.23	t	3,197,040.00	58,275,645.12
C	Structural steel wide-flange beams, W360X44 section	1.88	t	3,017,241.00	5,663,361.36
D	Structural steel wide-flange beams, W460X60 section	54.95	t	3,017,241.00	165,809,461.91
E	Structural steel wide-flange columns, W250X67 section	22.75	t	3,035,891.00	69,057,412.58
B3	**UPPER FLOORS**				
A	Formwork to edges of suspended slabs, not exceeding 250mm high	18.52	m²	5,071.00	93,930.13
B	Lightweight in-situ concrete topping to upper floor slab, 64mm thick (mix and reinforcement to be confirmed)	114.05	m³	143,896.00	16,411,626.59
C	Profiled metal decking to upper floor slab, 38mm deep	1,782.06	m²	17,985.00	32,050,259.18
B4	**STAIRS**				
A	1100mm high guard rail (material to be confirmed)	12.31	m	53,085.00	653,741.78
B	Formwork to soffits and sides of staircases	32.49	m²	13,293.00	431,876.28
C	In-situ concrete stair flight, 180mm max riser 280mm tread concrete pan (mix, reinforcement and finishes to be confirmed)	4.00	nr	3,729,314.00	14,917,256.00
D	Reinforced in-situ concrete (mix to be confirmed) in stairs; 180mm max riser, 280mm tread	153.19	m³	155,089.00	23,757,773.73
B5	**WALLS**				

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
A	152mm metal stud framing to external walls	1,643.12	m²	12,004.00	19,724,012.48
B	152mm metal stud framing to internal plumbing wall	40.38	m²	12,004.00	484,721.52
C	16mm Type-X fire-rated plasterboard lining to 1-hour rated partition	662.04	m²	15,294.00	10,125,270.35
D	16mm plasterboard lining to external walls	1,643.12	m²	11,898.00	19,549,841.76
E	16mm plasterboard lining to internal furring walls	883.32	m²	11,898.00	10,509,681.87
F	16mm plasterboard lining to internal partition	6,458.55	m²	11,898.00	76,843,875.49
G	16mm plasterboard lining to internal plumbing wall	80.76	m²	11,898.00	960,882.48
H	19mm plywood sheathing to external walls	1,643.12	m²	16,832.00	27,656,995.84
J	38mm metal furring to external walls	100.46	m²	3,388.00	340,368.64
K	38mm metal stud framing to internal furring walls	883.32	m²	4,129.00	3,647,207.64
L	42mm insulated panel to external walls (details to be confirmed)	100.46	m²	36,217.00	3,638,468.47
M	90mm facing brickwork in cement and sand (1:4) mortar to external walls	1,542.66	m²	58,015.00	89,497,303.87
N	92mm metal stud framing to 1-hour rated partition	331.02	m²	7,284.00	2,411,156.96
P	92mm metal stud framing to internal partition	3,229.28	m²	7,284.00	23,522,053.67
B6	**ROOF**				
A	EPDM membrane roofing on rigid insulation on metal deck (thicknesses and details to be confirmed)	199.73	m²	49,454.00	9,877,595.78
B	Standing seam metal roof covering (details to be confirmed)	1,850.94	m²	22,422.00	41,501,799.10
B7	**WINDOWS**				
A	Fixed glazed window, 1000 x 1000mm, glazed (frame material to be confirmed)	2.00	nr	154,107.00	308,214.00
B	Fixed glazed window, 1000 x 2000mm, glazed (frame material to be confirmed)	1.00	nr	295,330.00	295,330.00
C	Fixed glazed window, 1200 x 1500mm, glazed (frame material to be confirmed)	65.00	nr	267,086.00	17,360,590.00
D	Fixed glazed window, 3500 x 1000mm, glazed (frame material to be confirmed)	1.00	nr	507,165.00	507,165.00
B8	**DOORS**				
A	Double-leaf flush door set, 1830 x 2083mm, complete with ironmongery (material to be confirmed)	4.00	nr	453,311.00	1,813,244.00
B	Double-leaf flush door set, 1830 x 2134mm, complete with ironmongery (material to be confirmed)	2.00	nr	453,311.00	906,622.00
C	Single-leaf flush door set, 915 x 2134mm, complete with ironmongery (material to be confirmed)	87.00	nr	254,034.00	22,100,958.00
B9	**CEILING FINISHES**				
A	12mm plasterboard lining to suspended ceilings	38.10	m²	9,717.00	370,266.28

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
B	600 x 600mm acoustic ceiling tiles, 16mm thick to suspended ceilings	3,078.16	m²	17,475.00	53,790,846.00
C	Metal framing to suspended ceilings	38.10	m²	7,488.00	285,330.24
B10	**FITTINGS AND FURNISHINGS**				
A	25mm laminate toilet partition, ivory matte finish, complete with ironmongery (details to be confirmed)	20.59	m²	90,993.00	1,873,818.85
B	900mm high handrail, handrail only (material to be confirmed)	34.78	m	41,114.00	1,430,027.15
C	900mm high pipe guard rail (material to be confirmed)	9.37	m	42,538.00	398,368.37
D	Counter top, 600mm deep (material to be confirmed)	2.00	m	62,842.00	125,684.00
E	Counter top, 600mm deep, with sink hole (material to be confirmed)	3.00	m	62,842.00	188,526.00
F	Grab bar, type 8370-001300 (size and material to be confirmed)	4.00	nr	43,758.00	175,032.00
G	Grab bar, type 8370-001420 (size and material to be confirmed)	4.00	nr	43,758.00	175,032.00
H	Mirror, supplied and fixed (size to be confirmed)	2.00	nr	6,300.00	12,600.00
J	Mirror, type 24384 x 12192 (size to be confirmed)	2.00	nr	6,300.00	12,600.00
K	Mirror, type 9144 x 12192 (size to be confirmed)	1.00	nr	6,300.00	6,300.00
L	Semi-recessed towel dispenser with receptacle, 330mm wide (material to be confirmed)	5.00	nr	212,650.00	1,063,250.00
M	Vanity cabinet with double door sink unit, 1000mm wide (material to be confirmed)	5.00	nr	211,239.00	1,056,195.00
	TOTAL OF BILL B CARRIED TO SUMMARY				**900,123,102.77**

BILL C: M&E; SERVICES

Item	Description	Qty	Unit	Rate (₦)	Amount (₦)
C1	**PLUMBING AND DRAINAGE**				
A	Water heater, 380 L capacity, supplied and installed	1.00	nr	2,735,339.00	2,735,339.00
C2	**MECHANICAL INSTALLATIONS**				
A	Air-cooled screw chiller, 633-703kW capacity, supplied and installed	1.00	nr	210,292,425.00	210,292,425.00
B	Inline circulator pump, 3.9 LPS - 0.8 metre head, supplied and installed	1.00	nr	3,954,668.00	3,954,668.00
C	Rooftop upblast centrifugal fan, 991-1905 LPS, supplied and installed	1.00	nr	5,435,168.00	5,435,168.00
D	Split system horizontal air handling unit, supplied and installed (capacity to be confirmed)	2.00	nr	15,361,920.00	30,723,840.00
C3	**ELECTRICAL INSTALLATIONS**				
A	Lighting and appliance panelboard, 225A, supplied and installed	9.00	nr	494,949.00	4,454,541.00
B	Lighting point: PVC conduit, wiring, switch and back box, with pendant linear light fitting, 2-lamp, 1200mm	2.00	nr	86,094.00	172,188.00
C	Lighting point: PVC conduit, wiring, switch and back box, with pendant linear light fitting, 2-lamp, 2400mm	12.00	nr	159,014.00	1,908,168.00
D	Lighting point: PVC conduit, wiring, switch and back box, with plain recessed light fitting, 600 x 1200mm	269.00	nr	121,099.00	32,575,631.00
E	Lighting point: PVC conduit, wiring, switch and back box, with plain recessed light fitting, 600 x 600mm	47.00	nr	82,511.00	3,878,017.00
F	Single pole lighting switch, complete with conduit, wiring and back box	94.00	nr	8,390.00	788,660.00
G	Three way lighting switch, complete with conduit, wiring and back box	5.00	nr	8,941.00	44,705.00
H	Transformer switchboard, supplied and installed (rating and size to be confirmed)	2.00	nr	5,394,312.00	10,788,624.00
C4	**LIFT INSTALLATIONS**				
A	Hydraulic lift, 3500 lbs capacity, supplied and installed	1.00	nr	96,706,575.00	96,706,575.00
B	Lift landing doors, centre opening, 48" x 84"	2.00	nr	4,338,705.00	8,677,410.00
	TOTAL OF BILL C CARRIED TO SUMMARY				**413,135,959.00**